EXPERTWORX

Room renovation materials list

4.8 × 3.6 m room · 2.4 m wall height

Ceiling lining

17.28 m² ceiling, 2 by 3 sheet positions, 10% sheet allowance

Plasterboard sheets	**7 × 1.2 × 2.4 m**

Confirm sheet direction, joint support and fixing schedule. Price the specified screws, tape, joint compound or skim and edge trim with the supplier.

Plasterboard partition

3.6 m × 2.4 m, 1 opening(s), 2 face(s) × 1 layer(s), 10% sheet allowance

Plasterboard sheets	**7 × 1.2 × 2.4 m**
Studs before door framing	**7 at 600 mm spacing**
Top and bottom rails or track	**7.2 m gross**
Insulation	**2 pack(s), 6 m² each**

Sheet coverage is gross to allow cuts around doors. Confirm support, extra door framing, bracing, fixings, tape and compound against the specified assembly.

Room wall paint

37.17 m² net, 2 coats at 12 m²/L, 10% allowance, 3.15 m² openings deducted

Topcoat (6.81 L estimated)	**3 × 2.5 L tin**
Primer (4.09 L estimated)	**2 × 2.5 L tin**

Primer uses one coat at 10 m²/L. Confirm coverage and pack sizes on both labels.

Ceiling paint

17.28 m² net, 2 coats at 12 m²/L, 10% allowance

Topcoat (3.17 L estimated)	**2 × 2.5 L tin**
Primer (1.9 L estimated)	**1 × 2.5 L tin**

Primer uses one coat at 10 m²/L. Confirm coverage and pack sizes on both labels.